

Existing hedges and planting to retained as part of final

Hedge & Tree Removal

Although the hedgerows around the site are of limited ecological value, the western boundary does contain some semi-mature native tree species including field maple and hawthorn which are to be retained where possible. The remaining poor quality hedge and trees are to be removed and replaced.

Existing Hedges & Trees to be Removed

Existing hedges and planting to be removed to facilitate construction of new development.

Trees and hedges should not be removed during the bird nesting season (March-August). If this is not possible, then all trees and hedges must be inspected by an Ecologist prior to their removal. If an active nest is identified, the tree or section of hedge must be retained until the young have fledged and left the nest before removal.

Proposed Planting Details & Specification

All areas of new landscaping to have the existing topsoil and subsoil decompacted by hand digging or rotorvator. If any imported topsoil is required it should be placed to a depth of 350mm minimum in shrub areas and 200mm in grass areas and comply with BS3882:2007 Specification for Topsoil and Requirements for Use.

Planting should take place during the dormant planting season ie October to March. Indigenous species selected for seasonal interest and biodiversity.

incorporating compost at 1m³ per 3m³ of soil excavated and secured with timber stake and rubber tie.



New Tree Planting (122 no.)

3.5-4.25m high, 12-14 cm girth "Heavy Standards" root balled trees (supplied by Barcham Trees or similar approved) with 1.75-2.0m clear stem to be pit planted including underground guying to secure the tree in an upright position and "root deflection" system near paved areas including bulky organic compost mixed backfill.

Acer campestre (Field Maple) - Ac Acer platanoides "Crimson King" (Purple Maple) - ApCK Acer platanoides "Princeton Gold" (Gold Maple) - ApPG Alnus cordata (Italian Alder) - Ac Betula pendula (Silver Birch) - Bp Corylus avellana (Hazel) - Ca Prunus padus 'Albertii' (Cherry) - Pp Prunus sargentii 'Rancho' (Cherry) - Ps Pyrus calleryana "Chanticleer" (Flowering Pear) - Pc Quercus palustris (Pin Oak) - Qp Quercus robur (English Oak) - Qr Sorbus aria 'Majestica' - (Whitebeam) - SaM Sorbus aucuparia "Sheerwater" (Rowan) - Sa

Tilia cordata 'Green Spire' (Lime) - Tc

tilth, including Enmag fertilizer applied and worked into to 100m, rake and bring to given levels, remove all stones and debris over 50mm, dig planting holes (average 300 x 300 x 300 deep), supply and plant specified shrubs and plants in densities specified, backfill with excavated material as above, water in and mulch with 75mm bark chippings 20-40mm size. Water and weed regularly for 12 months and replace railed plants.



Native Hedge (maintained at 1.2m height)

Hedging to be pit planted in a double staggered row at 0.6m centres, plants to be supplied in as 80-100cm bareroot nursery stock.

65% Crateagus monogyna (Hawthorn) 10% Prunus spinosa (Blackthorn) 10% Acer campestre (Field Maple) 5% Cornus sanguinea (Dogwood) 5% Euonymus europaeus (Spindle) 5% Viburnum opulus (Guelder Rose)



Evergreen Hedge Planting

Plants to be pit planted 4 per m². Planted to provide a low growing swathe of ground cover. All plants to be 3 litre pot grown stock, planted in blocks of the same species as indicated on the drawing.

100% Prunus Laurocerasus 'Otto Luyken' (Laurel)

Evergreen Climbers

Shrubs to be pit planted 5 per m². Planted to provide cover to the fencing. All plants to be 5 litre pot grown stock, planted in groups of 7, 9 or 13 plants of same species.

35% Lonicera periclymenum (Honeysuckle) 35% Hedera helix 'Glacier' (White variegated) 30% Clematis (Old man's beard)

Shrub Planting

Shrubs to be pit planted at densities indicated, to provide ground cover, low maintenance shrub/flowering plant areas, to the following specification:



Evergreen Ornamental Shrubs

Shrubs to be pit planted 4 per m². Planted to provide low maintenance, colourfull, dense low growing shrubs. All plants to be 3 litre pot grown stock, planted in groups of 7, 9 or 13 plants of same species.

20% Euonymus fortunei 'Emerald and Gold' 20% Ceanothus 'Blue Mound' 20% Hypericum 'Hidcote' 20% Spirea japonica 'Goldflame' 20% Skimmia japonica 'Rubella'



Ground Cover Planting

Plants to be pit planted 4 per m². Planted to provide a low growing swathe of ground cover. All plants to be 3 litre pot grown stock, planted in blocks of the same species as indicated on the drawing.

Hebe 'Red Edge' - Hr Hebe pinguifolia 'Sutherlandii' - Hp Pachysandra terminalis - Pt

annum to allow grass to grow taller and flower throughout the year.



Close Mown Grass Areas

Grass areas to be seeded with amenity grass mix (A19 by Germinal or similar approved) containing a mix of fescue, ryegrass and bent



Grass areas to be seeded with sports field mix (A9 by Germinal or similar approved) containing a mix of ryegrass,

fescue and smooth stalk meadowgrass **Grassland Wildflower Areas**



Grass areas to be seeded with species rich grassland/ wildflower mix (WFG15 Countrylife, Schools & Colleges mix by Germinal or similar approved) contains a diverse range of

wildflower species from April - September in an 80:20 mix of grasses and native wildflowers including Shepherds Purse, field Poppy and Cornflower. Ideal for educational use for identifying native wildflowers.

Grass Maintenance

General Grass Areas - to be mown regularly throughout the growing season to ensure a low cut sward.

Sports Pitches - to be mown regularly throughout the season to ensure a low cut sward suitable for playing sports


Grassland Wildflower Areas - should not be mown during spring and summer until the wild flowers have seeded.

Fencing

1.8m high security fencing

1.2m high fencing

External school areas to be tarmac surfaced



Safety Surfacing

Biodiversity Enhancement

The following ecological enhancement has been included in the landscaped design as per Ecologist Recommendations (to be read in conjunction with Encon Associates Ecological Report)

- 2 x Schwegler 1SP sparrow terrace boxes on new buildings, to be located immediately beneath the eaves of the buildings, facing between north and east
- 2 x Eco Starling Nest Box recycled plastic weatherproof outer shell protecting a wooden nesting chamber with a 45mm entrance hole. ideal for starlings, who tend to favour higher nest sites so should be placed 2.5m or higher above the ground on the building fixed to the wall with three concealed mounting holes in the back of the box and face between north and east
- 2 x wooden Kent bat boxes, to be fixed 5-7m high on existing mature trees to face a variety of different directions, and can be located on the same tree or different trees. Ensure a clear 1m drop beneath each box, and do not place boxes where they will be illuminated at night
- 3 x different bug boxes / log piles of any design, to be located within areas of species rich planting

Plant native hedging containing 6 different species (1,200 liner metres)

Establish areas of species rich meadow within the open grassland (containing 35

Plant new trees within the site boundaries, to be native or of recognized value to wildlife by virtue of fruits and flowers (122 trees)

© Encon Associates - DISCLAIMER:

■ This drawing is copyright and shall not be reproduced nor used for any other purpose without the written permission of Encon Associates ■ This drawing must be read in conjunction with all other related drawings and documentation ■ It is the contractors responsibility to ensure full compliance with the relevant Regulations ■ Until technical approval has been obtained from the relevant Authorities it should be understood that all drawings issued are PRELIMINARY and NOT for Construction ■ Should the contractor start site work prior to approval been given, it is entirely at his own risk \blacksquare Do not scale from this drawing, use figured dimensions only \blacksquare It is the contractors responsibility to check and verify all dimensions on site ■ Any discrepancies to be reported to Encon Associates immediately

All survey information is provided by the surveying company and Encon Associates cannot accept any liability for any discrepancies there in
All survey information to be verified on site by Contractor ■ For our Standard Terms and Conditions, please visi www.enconassociates.co.uk/terms
Alternatively, a hard copy can be posted to you

Notes:

Key to Tree Existing Trees

In accordance with the Arboricultural Impact Assessment, the quality of the existing trees to be retained are indicated



Class B







Trees to be removed

Tree Removal

In order to prevent disturbance of nesting birds, any hedgerow removal (e.g. to create access) should be carried out outside of the bird nesting season (typically March to August). If this is not possible, any vegetation to be removed should be searched for the presence of active nests immediately prior to clearance. If a nest is found this should be retained in situ until the nestlings have fledged. Similarly, mobilisation of plant should take place outside of the nesting bird season to prevent the disturbance of groundnesting birds. If this is not possible, a survey should be undertaken to identify any active nests on the site, immediately prior to work starting. If a nest is found, works should be delayed until the nestlings have fledged.

P6 11.07.19 Pedestrian crossing and access updated P5 14.03.19 Bird box moved. Car share and EV added GM P4 14.03.19 Scooter note added. Buffer zone gate added NK P3 08.02.19 Amended in line with Planners comments NK P2 07.11.18 Redline boundary removed as requested GM P1 17.10.18 Cycle parking increased to 180 spaces MJB GM

Rev Date Description Drawn Checked Client

RG Carter / Cambridgeshire County Council

Buxhall Farm School

Glebe Way Histon and Impington, Cambridgeshire

Landscape & Biodiversity Plan

Drawing Status FOR PLANNING APPROVAL

Drawn Checked GM MJB

Scale (A1) 1:500 08.10.18



NG5 7DR ■ T: 0115 987 55 99 ■ E: enquiries@enconassociates.co.uk ■ W: www.enconassociates.co.uk Environmental Consultants to the Construction Industry

Head Office

Nottingham

10 Chapel Lane

■ BREEAM ■ Code for Sustainable Homes Assessors ■ Landscape Architecture ■ Highway Engineers ■ Life Cycle Costing ■ Energy Assessment ■ SAP ■ EPC ■ SBEM ■ Daylight Calculations

Rev Job Number Drawing Number A3563 07