



Notes:

1. New access track to have a rolled stone surface with grass verges as shown, wider on bends and to allow for passing.
2. See separate specification and schedule for planting details.
3. Individual tree planting to be feathered or heavy standard trees, planted into prepared pits and staked - native species around perimeter, more variation within the site, detailed arrangement of species to be determined on site.
4. Woodland edge planting to be native species transplants at 1.5m centres, with some feathered trees.
5. Hedge Type 1 to site perimeter, outside access track, to be double staggered row of native species. Hedge maintained to an ultimate height of 3m.
6. Hedge Type 2, to inside of access track, to be double staggered row of beech, maintained to an ultimate height of 2m. 1.2m high green mesh windbreak fencing to be erected between the hedge and the track to provide some shelter for the plants and initial screening until the hedge becomes established.
7. Woodland edge and hedge planting to be protected from rabbit damage by individual plant shelters - see specification.
8. All planting to take place within the November to March planting season, establishment maintenance for five years after planting to include replacement of dead or failed plants.

-  Existing trees and hedges
-  Proposed tree planting
-  Proposed woodland edge planting
-  Proposed hedges

Rev. B, April 2016 - revised line to SW boundary
 Rev. A, April 2016 - trees added to NW corner

project Vetspeed, A505, Cambridgeshire		
file		
PLANTING PROPOSALS		
Jon Echells Consulting Devonshire Business Centre Works Road Letchworth Herts SG6 1GJ 01462 488221	date December 2015 scale 1: 750 @ A3	checked je dwg. no. JEC/407/01B

New section of path with relocated raised brick beds and new tree planting, to replace lost area of garden